## MYSORE RAILWAYS, HASSAN.

*Notification dated 4th November 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 2 P. M., on 1st December 1930, for providing convenience for traffic and Engineering Staff at Hosahalli Station on Tarikere-Narasimharajapura Tramway. An approximate estimate of quantities is given in the following Schedule. The quantities are not guaranteed. The work should be completed by the end of 30th May 1931, showing continuous equal monthly progress.

2. Detailed estimates and plans and conditions of schedule agreement, may be seen at the Executive Engineer's Office at Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer, on payment of one rupee.

4. Every tender must be accompanied by a deposit of Rs. 100 in cash as earnest money and should be superscribed "Tenders for providing convenience for Traffic and Engineering Staff at Hosahalli Station on Tarikere-Narasimharajpura Tramway," in default of which tenders will be rejected.

5. The earnest money of rejected tenderers will be returned as early as possible after the tenders are disposed of and in the case of accepted tender it would be held as a part of security under clause 4 of the schedule agreement referred to.

6. The final acceptance of any tender will rest with the Engineer-in-Chief, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled.

9. Definite rates against each item of work in the schedule should be noted both in figures and in words.

*Schedule.*

| | Item of work | Unit | Quantity |
|---|---|---|---|
| | Staff well 5 feet in dia. at Hosahalli Station.— | | |
| 1 | Earthwork excavation in hard gravel 1st fathom ... | C.yd. | 8 |
| 2 | Do in soft rock 1st do ... | ,, | 8 |
| 3 | Do do 2nd do .. | ,, | 8 |
| 4 | Do in hard rock 2nd do .. | ,, | 8 |
| 5 | Do do 3rd do ... | ,, | 15 |
| 6 | Do do 4th do ... | ,, | 5 |
| 7 | Do do 5th do ... | ,, | 5 |
| 8 | Do do 6th do ... | ,, | 5 |
| 9 | Do do 7th do ... | ,, | 5 |
| 10 | Steining with dry stone including jelly packing 6" thick .. | 100 C.ft. | 800 |
| 11 | Burnt stone masonry in mortar ... ... | ,, | 77 |
| 12 | Burnt stone slabs 6" thick dressed and fixed in mortar ... | S.ft. | 31 |
| 13 | One wooden pully including fixing ... ... | No. | 1 |
| 14 | Pointing with mortar ... ... | 100 S.ft. | 360 |
| 15 | Bailing water per foot depth of excavation below spring level | ... | ... |
| | II. Providing a bath room with compound wall to the out-house attached to Station building.— | | |
| 1 | Earthwork excavation for walls and filling in basement ... | 1,000 C.ft. | 240 |
| 2 | Concrete broken stone in mortar .. .. | 100 C.ft. | 60 |
| 3 | Burnt brick in mortar in founds ... ... | ,, | 220 |
| 4 | Do in superstructure ... ... | ,, | 50 |
| 5 | Burnt brick in mud ... .. | ,, | 350 |
| 6 | Plastering with mortar .. ... | 100 S.ft. | 880 |
| 7 | White and colour washing .. ... | ,, | 880 |
| 8 | Teakwood doors battened with frames, fittings, etc., complete. | S.ft. | 36 |
| 9 | Teakwood windows battened with frames, fittings, iron bars, etc., complete. | ,, | 6 |
| 10 | Burnt stone slabs 6" thick dressed and fixed in mortar ... | ,, | 18 |
| 11 | Teakwood wrought and put up including wood oiling, etc., complete. | C.ft. | 8·43 |
| 12 | Roofing with First Class Mangalore tiles over teak reepers, wind ties, chunam borders, etc., complete. | 100 S.ft. | 202 |

*Schedule.*

| | Item of work | Unit | Quantity |
|---|---|---|---|
| 13 | Mangalore ridge tiles set in mortar ... ... | R.ft. | 13 |
| 14 | Painting with chocolate paints two coats ... ... | 100 S.ft. | 70 |
| 15 | Flooring with Cuddapah slabs 1½" to 2" thick over 3" concrete including cement pointing, etc., complete. | ,, | 160 |
| 16 | Providing sinks and ovens ... ... | No. | 2 |
| 17 | Providing masonry drains 6" x 6" with 4½" bricks in mortar side walls over 6" concrete in mortar including plastering with cement, etc., complete. | R.ft. | 20 |
| III. | Constructing one block of two units for menials at Hosaballi Station:— | | |
| 1 | Earthwork excavation and filling in basement .. | 1,000 C.ft. | 403 |
| 2 | Concrete broken stone in mortar ... ... | 100 C.ft. | 403 |
| 3 | Burnt brick in mortar ... ... | ,, | 1,212 |
| 4 | Burnt stone slabs 6" thick dressed and fixed in mortar ... | S.ft. | 96 |
| 5 | Plastering with mortar ... .. | 100 S.ft. | 2,200 |
| 6 | White and color washing ... ... | ,, | 2,200 |
| 7 | Teakwood doors battened with frames, fittings, etc., complete. | S.ft. | 36 |
| 8 | Teakwood windows and ventilators battened with frames, fittings, iron bars 5/8" round fixed at 4" centres, etc., complete. | ,, | 16 |
| 9 | Teakwood work wrought and put up including wood oiling, etc., complete. | C.ft. | 26·91 |
| 10 | Roofing with First Class Mangalore tiles over teak reepers including chunam borders and wind ties, etc., complete. | 100 S.ft. | 633 |
| 11 | Mangalore ridge tiles set in mortar ... ... | R.ft. | 27 |
| 12 | Painting with chocolate paint two coats ... ... | 100 S.ft. | 130 |
| 13 | Flooring with gravel 6" thick well rammed ... ... | ,, | 275 |
| 14 | Providing sinks and ovens ... ... | No. | 4 |
| 15 | Do teakwood planks for shelves 1" thick .. | S.ft. | 5 |
| 16 | Coat racks of teakwood ... ... | No. | 2 |
| 17 | Providing masonry drains 6" x 6" with 4½" brick in mortar side walls over 6" concrete in mortar including plastering with cement, etc., complete. | R.ft. | 80 |
| 18 | Earthwork excavation for catch water drains ... | 1,000 C.ft. | 8,000 |
| IV. | Constructing one block of Gang Huts of 4 units at Hosahalli— | | |
| 1 | Earthwork excavation ... ... ... | 1,000 C.ft. | 600 |
| 2 | Burnt brick in motar ... ... ... | 100 C.ft. | 990 |
| 3 | Burnt brick in clay ... ... ... | ,, | 990 |
| 4 | Burnt stone slabs 6" thick dressed and uxed in mortar .. | S.ft. | 120 |
| 5 | Plastering with mortar .. ... .. | 100 S.ft. | 2,400 |
| 6 | White washing 2 coats ... ... ... | ,, | 2,400 |
| 7 | Teakwood doors battened with fames, fittings, etc., complete. | S.ft. | 72 |
| 8 | Teakwood windows battened with fames, fittings, iron bars 5/8" round fixed at 4" centres, etc., complete. | ,, | 35 |
| 9 | Teakwood wrought and put up including wood oiling .. | C.ft. | 35·10 |
| 10 | Roofing with 1st Class Mangalore tiles over teak reepers including chunam borders and wind ties, etc., complete. | 100 S.ft. | 360 |
| 11 | Mangalore ridge tiles set in mortar ... ... | R.ft. | 42 |
| 12 | Painting with chocolate paint, 2 coats ... ... | 100 S.ft. | 250 |
| 13 | Flooring with gravel 6" thick well rammed ... ... | ,, | 400 |
| 14 | Providing sinks and Ovens ... ... | No. | 4 |
| 15 | Providing masonry drains 6" x 6" with 4½" side walls of brick in mortar over 6" concrete including plastering with cement, etc., complete. | R.ft. | 40 |
| 16 | Earthwork excavation for catch water drains ... | 1,000 C.ft. | 8,000 |

M. RAMAIYA,
*Executive Engineer.*